

Zeitschrift: IABSE congress report = Rapport du congrès AIPC = IVBH
Kongressbericht

Band: 10 (1976)

Artikel: Field observation of long span bridge foundation designed on the
results of models tests

Autor: Suzuki, S. / Ishimaru, M. / Nemoto, F.

DOI: <https://doi.org/10.5169/seals-10545>

Nutzungsbedingungen

Die ETH-Bibliothek ist die Anbieterin der digitalisierten Zeitschriften auf E-Periodica. Sie besitzt keine Urheberrechte an den Zeitschriften und ist nicht verantwortlich für deren Inhalte. Die Rechte liegen in der Regel bei den Herausgebern beziehungsweise den externen Rechteinhabern. Das Veröffentlichen von Bildern in Print- und Online-Publikationen sowie auf Social Media-Kanälen oder Webseiten ist nur mit vorheriger Genehmigung der Rechteinhaber erlaubt. [Mehr erfahren](#)

Conditions d'utilisation

L'ETH Library est le fournisseur des revues numérisées. Elle ne détient aucun droit d'auteur sur les revues et n'est pas responsable de leur contenu. En règle générale, les droits sont détenus par les éditeurs ou les détenteurs de droits externes. La reproduction d'images dans des publications imprimées ou en ligne ainsi que sur des canaux de médias sociaux ou des sites web n'est autorisée qu'avec l'accord préalable des détenteurs des droits. [En savoir plus](#)

Terms of use

The ETH Library is the provider of the digitised journals. It does not own any copyrights to the journals and is not responsible for their content. The rights usually lie with the publishers or the external rights holders. Publishing images in print and online publications, as well as on social media channels or websites, is only permitted with the prior consent of the rights holders. [Find out more](#)

Download PDF: 23.02.2026

ETH-Bibliothek Zürich, E-Periodica, <https://www.e-periodica.ch>

Field Observation of Long Span Bridge Foundation Designed on the Results of Models Tests

Mesures in situ sur les fondations d'un pont de grande portée dimensionnées sur la base d'essais sur modèle

Messungen an Foundationen einer weitgespannten Brücke, welche auf Grund von Ergebnissen von Modellversuchen bemessen wurden

S. SUZUKI

Chief

Hamana By-Pass Construction Office, Japan Highway Public Corporation
Tokyo, Japan

M. ISHIMARU

Project Engineer

F. NEMOTO

Manager, Hamana Ohbashi Construction Office
Kajima Corporation
Tokyo, Japan

Y. NOJIRI

Assistant Head, Civil Eng. Dept.
Kajima Institute of Construction Technology
Tokyo, Japan

1. Introduction

The main caissons of HAMANA Bridge was designed on the results of model tests, because the method of designing such a multi-cell caisson had not been established yet, as is stated in the Preliminary Report "Model Test for Design of Long Span Bridge Foundation" written by the authors. The caissons were sunken in March 1974 and the construction of superstructure was completed in August 1976. During the construction, the stress of one of these caissons was measured and compared with the results of model tests in order to confirm an actual state of the caisson designed in this way.

This paper shows the method of measurement and consideration of the result of measurement.

2. Instruments

Strain-gages and reinforcement-stress-gages, which are all Carlson type gages, were embedded in four sections, i.e. 12 strain-gages were embedded in the lower part of the pier to check the load from superstructure; 2 strain-gages and 6 reinforcement-stress-gages, in the top and the bottom of the slab to know its bending; 8 strain-gages, in the upper part of the bulkheads to know the transmission of load. In each section, a null-stress-gage was embedded in order to cancel the effects of creep or drying shrinkage in the measured data.

3. Loads under Consideration

The measurement was conducted for 21 months from the beginning of construction of the pier to the completion of the girder. The loads in this period consisted of the vertical load and the moment load which came through the pier. The vertical load was gradually increasing by the selfweight of pier and girder. The moment load, which was caused by the unbalanced weight of the main and side girders fluctuated according to the stage of construction of the girders.

The maximum values of these loads per one pier were 12,000ton and 27,000 ton-m respectively.

4. Results and Consideration

The measured strains were compared with calculated strains which were obtained by applying the strain-load relation based on the model tests to the




Photo. 1 Nearly Completed HAMANA Bridge

estimated loads depending on the stage of construction.

The strains detected at the pier showed good agreement with the calculated strains. This means that the slab of the casson was loaded by the just load as was estimated. The strains detected at the slab and the bulkheads also showed good agreement. This fact strongly supports the conception which was used in the design.

Considering the state of the slab, which was regarded as of great importance in the design, it can be considered that no tension cracks occurred in the concrete during construction, because the maximum tension strain near the lower surface was $70\sim 90 \times 10^{-6}$ and less than the general cracking strain of concrete. This also means that the slab will not crack under service loads, because the loads in these two conditions are almost equal.

Through the above study it has been certified that the calculated strains agree with the measured strains unless the slab cracks. But under the design load during earthquake, the slab will crack and its bending stiffness will reduce, therefore, the stress distribution is different from the results of model tests. In order to deal with this effect of cracking, Finite Element Method(F.E.M.) mentioned in the preliminary report had been used. Depending on the result, the reduction of bending stiffness of the slab resulted in slight increase of vertical stress in the bulkheads beneath the pier while the bending moment of the slab decreased. And in the actual design this increase of vertical stress had been estimated with sufficient safety.




Fig.1 Caisson of
HAMANA Bridge




Photo. 2 Caisson under Construction

SUMMARY

After the multi-cell type huge caisson of HAMANA Bridge had been designed on the results of model tests as is stated in the Preliminary Report, the stress measurement during construction was carried out to know the actual state of these caissons. The results of measurement showed good agreement with the designed values and the validity of this design method was certified.

RESUME

Les caissons multicellulaires en béton armé des fondations du pont de HAMANA ont été dimensionnés sur la base d'essais sur modèle (voir Rapport Préliminaire). Les auteurs ont pratiqué une série de mesure de contraintes pendant la construction pour connaître l'état réel du caisson. Les résultats montrent une bonne correspondance avec les valeurs calculées, ce qui prouve la validité de la méthode de calcul employée.

ZUSAMMENFASSUNG

Nachdem die vielzelligen Senkkästen der HAMANA Brücke auf Grund von Ergebnissen von Modellversuchen bemessen worden waren (siehe Vorbericht), wurden Baustellen-Messungen durchgeführt, um das tatsächliche Verhalten dieser Senkkästen zu untersuchen. Die Ergebnisse der Messungen zeigen gute Uebereinstimmung mit der Berechnung, wodurch die Gültigkeit dieser Bemessungsmethode nachgewiesen werden konnte.

Leere Seite
Blank page
Page vide