

Zeitschrift: IABSE congress report = Rapport du congrès AIPC = IVBH
Kongressbericht

Band: 10 (1976)

Artikel: Design and construction of the Hokawazu Bridge

Autor: Miyazaki, Yujiro

DOI: <https://doi.org/10.5169/seals-10402>

Nutzungsbedingungen

Die ETH-Bibliothek ist die Anbieterin der digitalisierten Zeitschriften auf E-Periodica. Sie besitzt keine Urheberrechte an den Zeitschriften und ist nicht verantwortlich für deren Inhalte. Die Rechte liegen in der Regel bei den Herausgebern beziehungsweise den externen Rechteinhabern. Das Veröffentlichen von Bildern in Print- und Online-Publikationen sowie auf Social Media-Kanälen oder Webseiten ist nur mit vorheriger Genehmigung der Rechteinhaber erlaubt. [Mehr erfahren](#)

Conditions d'utilisation


L'ETH Library est le fournisseur des revues numérisées. Elle ne détient aucun droit d'auteur sur les revues et n'est pas responsable de leur contenu. En règle générale, les droits sont détenus par les éditeurs ou les détenteurs de droits externes. La reproduction d'images dans des publications imprimées ou en ligne ainsi que sur des canaux de médias sociaux ou des sites web n'est autorisée qu'avec l'accord préalable des détenteurs des droits. [En savoir plus](#)


Terms of use

The ETH Library is the provider of the digitised journals. It does not own any copyrights to the journals and is not responsible for their content. The rights usually lie with the publishers or the external rights holders. Publishing images in print and online publications, as well as on social media channels or websites, is only permitted with the prior consent of the rights holders. [Find out more](#)

Download PDF: 08.08.2025

ETH-Bibliothek Zürich, E-Periodica, <https://www.e-periodica.ch>





(1) Intent of the design

Reinforced concrete arch bridges are generally constructed with the help of stagings such as "arch center". But in this bridge, a cantilever construction method was adopted, in which the constructing segments formed of an arch, struts and floor slabs were supported by prestressing bars and, therefore, it was necessary to analyze each of the struts and the floor slabs as well as the arch rib, as a part of a cantilevered structure.

The design calculation by a computer with a large capacity was made for every temporary structural system corresponding to the growth of the arch rib, struts and slabs, conditions of falsehood and other equipment, as well as for the final structural system.

(2) Outline of the design

1) Arch rib

The arch rib, with a cross section of two boxes, was designed as two hinged structure. The span length and the rise of the arch are 170 m and 26.5 m, respectively. The arch rib has a height of 3.0 m at its springings, 2.4 m at the crown, and has a width of 8.0 m except the portions of the nearest 19 m from the springings where it was increased lineally from 8.0 m to 16.0 m providing the maximum at the springings for the reason of improvement of stability against lateral seismic and wind forces perpendicular to the bridge axis.

2) Struts and piers

Struts on the arch rib range from 17.951 m to 0.635 m in their heights, and were designed as rigid frame structures of one to five stories. Top and bottom ends of each strut have steel pin bearings so that the strut can behave as a rocking pier absorbing the large amount of bending moments due to the inclination of the strut by the over-raising of the structure during the construction and by the influence of temperature changes, creep and shrinkage of the concrete.

3) Floor Slab

Continuous hollow slab, over nine spans and 60 cm thick, were adopted because it was important to decrease the dead weight of the slab in such cantilever construction.

4) Abutments

Abutments of large dimensions at both ends of the bridge were necessary as anchorages against the overturning of the cantilevered structural parts during the construction, and such large dimensions are not necessary for the stability of the bridge after the completion.

5) Abutments for arch rib

The maximum axial compressive force in the arch rib at its springings is approximately 5000t at the time of construction and 6700t at the final stage of completion. The axial force is transmitted to the abutment for the arch rib through a large bearing which consists of four steel pin bearings.


The dimensions of the abutments reach 20 m in width, 9 m in height and 8 m in length.

Construction


(1) Construction process


1) Construction of side spans

- i. Concrete placing for abutments and piers
- ii. Placement of 76 prestressing steel bars on the surface of the floor slabs.
- iii. Placement of four bearings (capable of 1655t reaction by a bearing) for the arch rib.



- 2) Construction of a part of the arch rib on suspended falseworks
 - i. Placement of steel panel girder falseworks suspended by 36 inclined prestressing steel bars, T_1 , in the portions between P_1 and P_2 .
- 3) Construction of the consecutive part of the arch rib on movable falseworks
 - i. Construction of the arch rib between P_1 and P_2 by cantilever construction method on the "Wagen".
 - ii. Construction of struts, P_2 , followed after the above stage.
 - iii. Construction of the floor slab between P_1 and P_2 on movable falseworks.
 - iv. Placement of 32 inclined prestressing steel bars, T_2 , and of prestressing steel bars on the floor slab between T_1 and T_2 .
 - v. Advancing the above processes and completing the arch rib except the arch crown.
- 4) Construction of the arch crown and re-movement of equipment and temporarily placed steel bars.





POSTSCRIPT

There have been a lot of reinforced concrete arch bridges since considerably old times. In every case of them the major problem to be solved was how to erect the structure. But we are sure that the erection method developed in this Hokawazu Bridge work can be a step to solve it. As arch-type bridge is a most hopeful structural system among concrete bridges of large span which are supposed to become very popular in future, we would be much pleased if the data of this bridge could greatly contribute the establishment of an effective erection method.

REFERENCES

- Y. Inoue and Y. Miyazaki: "Construction of the Hokawazu Bridge", Roads, February 1974
- Y. Miyazaki and T. Igarashi: "Design and Construction of the Hokawazu Bridge, (I) and (II)", Bridges and Foundations, Vol. 8, No. 7 & No. 8, 1974
- Mario d'Aragona: "La costruzione dell' arco del ponte Van Staden's in Sud Africa", L'Industria Italiana del Cemento, Anno XL1, dicembre 1971

SUMMARY

This paper describes a special method applied to the construction of a reinforce concrete arched bridge with a length of 252 m and a central span of 170 m. The conventional staging method is not employed in the bridge erection and the whole bridge is overhung from the two banks and connected at the central crown part.

RESUME

Cet article décrit un procédé spécial utilisé pour la construction d'un pont en arc en béton armé, de 252 m de long et d'une travée centrale de 170 m. On n'utilise pas la méthode classique de l'échafaudage dans la construction de ce pont. Le pont entier est construit en encorbellement à partir des deux rives.

ZUSAMMENFASSUNG

Dieser Bericht beschreibt ein Spezialverfahren, das beim Bau einer Bogenbrücke aus Eisenbeton mit einer Länge von 252 m und einer zentralen Spannweite von 170 m angewendet wurde. Die herkömmliche Gerüstaufstellung wird hier vermieden. Die ganze Brücke wird von den zwei Flussufern her vorgebaut und im Bogenscheitel verbunden.