Zeitschrift: IABSE congress report = Rapport du congrès AIPC = IVBH

Kongressbericht

Band: 11 (1980)

Artikel: The south abutment at Kessock Bridge, Scotland

Autor: Cole, K.W.

DOI: https://doi.org/10.5169/seals-11418

Nutzungsbedingungen

Die ETH-Bibliothek ist die Anbieterin der digitalisierten Zeitschriften auf E-Periodica. Sie besitzt keine Urheberrechte an den Zeitschriften und ist nicht verantwortlich für deren Inhalte. Die Rechte liegen in der Regel bei den Herausgebern beziehungsweise den externen Rechteinhabern. Das Veröffentlichen von Bildern in Print- und Online-Publikationen sowie auf Social Media-Kanälen oder Webseiten ist nur mit vorheriger Genehmigung der Rechteinhaber erlaubt. Mehr erfahren

Conditions d'utilisation

L'ETH Library est le fournisseur des revues numérisées. Elle ne détient aucun droit d'auteur sur les revues et n'est pas responsable de leur contenu. En règle générale, les droits sont détenus par les éditeurs ou les détenteurs de droits externes. La reproduction d'images dans des publications imprimées ou en ligne ainsi que sur des canaux de médias sociaux ou des sites web n'est autorisée qu'avec l'accord préalable des détenteurs des droits. En savoir plus

Terms of use

The ETH Library is the provider of the digitised journals. It does not own any copyrights to the journals and is not responsible for their content. The rights usually lie with the publishers or the external rights holders. Publishing images in print and online publications, as well as on social media channels or websites, is only permitted with the prior consent of the rights holders. Find out more

Download PDF: 21.10.2025

ETH-Bibliothek Zürich, E-Periodica, https://www.e-periodica.ch



XI

The South Abutment at Kessock Bridge, Scotland

La culée sud du pont de Kessock en Ecosse

Das südliche Widerlager der Kessock Brücke in Schottland

K.W. COLE BSc., MSc., FICE Ove Arup & Partners London, Great Britain

SUMMARY

The predictions of movement of a large bridge abutment, based on a consideration of the forces in the piles, indicated that it would move outwards and tilt forwards. However, taking into account the ground displacement due to the large mass of fill which was placed behind the abutment, inwards and backwards tilting movements were predicted. Since this latter mode of movement could have introduced undesirable stresses, the abutment movements were measured.

RESUME

La prévision des déplacements d'une culée de pont de grande taille, basée sur l'analyse conventionnelle des forces appliquées, indiqua que la culée se déplacerait et basculerait en avant. Cependant, en considérant toutes les forces, la grande masse de remblai placée derrière la culée étant inclue, un déplacement et un basculement vers l'arrière furent prévus. Comme ce dernier type de mouvement pouvait introduire des contraintes indésirables, les déplacements effectifs de la culée furent mesurés.

ZUSAMMENFASSUNG

Bezüglich der Bewegung eines grossen Widerlagers der Kessock Brücke in Schottland wurde vorausgesagt, es würde nach aussen gleiten und nach vorn kippen. Trotz Berücksichtigung der Bodenbewegungen und der grossen Füllmasse, die hinter dem Widerlager angebracht wurde, wird vermutet, dass das Widerlager nach innen gleiten und nach hinten kippen wird. Da dies unerwünschte Spannungen auslösen würde, sind an dem Widerlager Messungen durchgeführt worden.



1. INTRODUCTION

The Kessock Bridge when completed will span the Beauly Firth at Inverness, Scotland. As shown in Figure 1 the abutment to the southern approach viaduct retains a selected granular fill embankment some 12m high, and supports one end of the first 64m span. The bearings of the viaduct are designed to transmit vertical load only, longitudinal forces being absorbed in the piers and at the northern abutment.




Figure 1 Location and general details

2. DESIGN OF FOUNDATIONS

2.1 Soil conditions

The great depth of alluvial deposits at the site have influenced the choice of foundations; a borehole for a pier adjacent to the navigation channel reached 95m below bed level, and a borehole 1 km away reached 89m below ground level, both encountering only alluvial deposits. The alluvial deposits increase in density with depth and pad foundations have been adopted where maximum bearing pressures can be economically kept to within 250 kPa. Where bearing pressures exceed this, or the depth of construction below water exceeds 10.5m, steel H-section bearing piles have been driven into the alluvial deposits.

2. 2 Abutment foundations

Conventional analysis of the southern abutment foundation indicated that three rows of piles raked at 1 in 4, and a rear row of vertical piles were required to provide adequate support for the loads shown in Figure 2. The driving record of piles is given in Figure 1; test loading of a vertical pile gave 7mm settlement at the design working load of 1600 kN.

3. MOVEMENT OF THE FOUNDATIONS

3.1 Analysis treating only forces on abutment

Analysis of the movement of the abutment, taking account of the forces shown in Figure 2, and treating the piled foundation as elastic springs, showed that abutment movements would tend to be downwards and forwards, the base of the abutment moving some 40mm towards the north.




Figure 2 Loading diagram of forces on abutment (non-seismic loads)

However, it was evident that the analysis of movement of the abutment could not be considered in isolation from the ground movements that would be generated by the construction of the short length of granular fill embankment between the already placed embankment and the abutment.





Figure 3. Finite element model. For properties of materials 1 to 7 see Table 1.



A finite element programme, SAFE, (Reference 1) incorporating facilities to take account of soil and structural material properties was used to compute ground movements and stresses in the structural elements. Previous computations using the SAFE programme including modelling of anchored retaining walls, had shown that the programme gave reasonably accurate predictions of movements when compared with field measurements.

A two dimensional finite element model of the abutment and the soil was established, see Figure 3, and a series of analyses undertaken, the assumed soil and structural material properties for Analyses 3, 4 and 5 being shown in Table 1.

Table 1 "SAFE" finite element input data of material parameters.

All strength and modulus properties in MN/m

Material	Soil		Concrete	Piles		Soils	
parameters	(Analyses 3 & 4)		(All analyses)	(Analyses 3 & 5)		(Analysis 5)	
Material number	1	2	3	4	5	6	7
Material type	LE	LE	LE	LE	LE	LE(s)	LE(s)
Drainage	Drained	Drained	Drained	Drained	Drained	Drained	Drained
E_1	50	30	30 000	50	50	50	30
V12	0.3	0.3	0.1	0.3	0.3	0.3	0.3
E_2	50	30	30 000	4809	7642	50	30
\mathbf{v}_{12}	0.3	0.3	0.1	0.3	0.3	0.3	0.3
G ₁₂	19.20	11.54	13636	19.20	19.20	19.20	11.54
œ	0	0	0	-14.036	0	0	0
c†	_		_	_		0.017	0.017
ø۱	_	_	_	_		0	0

Note

LE = linear elastic model

LE(s) = linear elastic model with strength limitation

Drained = excess pore water pressures assumed dissipated

E₁, E₂ = principal Young's modulii in x, y plane, suffix 1 denoting horizontal (in plane),

2 denoting vertical and 3 denoting horizontal (normal to plane) directions

when &=0

G₁₂ = shear modulus between directions 1 and 2

= anticlockwise inclination of direction 1 to horizontal (degrees)


c' = cohesive resistance (limiting value)

ø' = frictional resistance (limiting value)


The soils were given linear elastic properties and assumed to be drained, since their rate of consolidation was expected to be rapid. The assumptions concerning the pile elements are stated in Figure 5; for Analysis 4 the piles were assumed to be absent in order to demonstrate the general validity of the method. The main defect of the model was that the pile elements had to be considered as having the same unit "depth" (of 1 metre) as the soil and concrete elements, thus prohibiting relative movement in the line of the bridge between the piles and adjacent soil.

3.3 Loading sequence

The loading sequence used is shown in Figure 4, the construction process being simulated by four stages, A to D. To check on the effect of the simplifying assumption that the embankment load applied only a vertical load, Stage Z in which horizontal shear loads from the embankment were applied was run in addition to Stage B in Analysis 3.



<u>Figure 4</u> Loading diagram for finite element model



ANALYSIS 3

Assumptions
Pile elements have correct
axial stiffness, are
anisotropic and are "connected"
to adjacent soil elements.

ANALYSIS 4

Assumptions
Pile elements deleted and replaced by soil.

ANALYSIS 5

Assumptions
Pile elements have correct
axial stiffness, are
anisotropic and "connections" to
adjacent soil elements have
shear strength limitation
cohesion=170kPa, \$\phi = 0\$

Figure 5 Computed and measured movements.



3. 4 Computed and measured movements

The results of the computations of movement are presented in diagrammatic form in Figure 5, with the measured results to date shown on Analysis 3. Studs X and Y on which level readings have been made are located on the road centreline at the positions shown in Figure 1. Site measurements of movement of the abutment in the line of the road were attempted, but showing little if any movement and being difficult to make with sufficient accuracy they were discontinued. The abutment movements have therefore been presented on the assumption that only vertical movement took place.

3.5 Movements were time dependent

The diagram giving settlement against time, Figure 6, shows that realisation of full settlement at each stage of loading was delayed by classical consolidation involving the dissipation of excess pore water pressures from the fine grained soils, complete dissipation for each stage taking about 6 months. The specified sequence of embankment filling was that Volume A should be completely placed in Stage B (Figure 4) before the placing of Volume B was started in Stage C, the object being to eliminate the pressure of fill material against the stem of the retaining wall as the base took up




Figure 6 Loading and settlement with time.

the major part of its backward rotation during the placing of Volume A, see Figure 5. In the event, the fill surface was raised uniformly over the entire fill length from about 5m above datum to 13m above datum in one continuous lift, followed by further filling to road base level at 17m above datum after a delay of two months.

4. EFFECT OF MOVEMENTS ON STRUCTURE

4.1 Restraint on backward rotation

As a consequence of following the described sequence of filling the lateral pressure of retained soil restrained the tendency of the base to tilt backwards by developing the bending strength of the connection between stem and base, the measured average angular rotation between the stem and base being about 1 in 900 after the filling to 13m above datum. During the subsequent filling this rotation increased to about 1 in 525, It is thought that the average vertical movements of base will have not been affected by the difference between the intended and the actual sequences of filling, but the backward tilt of the base may have been reduced.

4.2 Stiffening effect of piled foundation

From Figures 5 and 6 reasonably good correlations are apparent between the predicted settlement from Analysis 3 and the actual settlement on 17th January 1979, when the loading was the abutment base and stem (Stage A) and on 18th June 1979 when all loads except the bridge deck had been placed and consolidation under those loads was virtually complete (Stage C). It is evident that the piles moved together with the surrounding soil to give much greater settlements than could have been predicted from the results of the pile test loading and considerations of group action; the movements were of the same

K.W. COLE 1105

form but smaller than those that would have occurred if the foundation had not had piles. The smaller actual backward tilt than predicted by Analysis 5 indicates that the soil adjacent to the rear row of piles did not move differentially to the piles, and that shear failure played little part in the overall behaviour.

5. ACKNOWLEDGEMENTS

The Client is the Scottish Development Department who kindly gave their consent to the publication of this paper.

The Contractor is a consortium of Cleveland Bridge and Engineering Company and Redpath Dorman Long (Contracting) Ltd. The bridge was designed by Dr. Ing H. Homberg in association with Cleveland, and the substructure by Trafalgar House Engineering Services in association with R.D.L.

The Joint Engineers for the Client are Crouch and Hogg of Glasgow and Ove Arup and Partners of London

Acknowledgement is made of the dedication of the site staff in obtaining the readings which made possible this contribution.

6. REFERENCE

A computer model for the analysis of ground movements in London Clay. Simpson B., O'Riordan N.J. and Croft D. D. (1979). Geotechnique 29, No. 2, 149-175.

Leere Seite Blank page Page vide