

Zeitschrift: IABSE structures = Constructions AIPC = IVBH Bauwerke
Band: 3 (1979)
Heft: C-7: Structures in Switzerland

Artikel: Swiss railways' double track Aar Bridge at Ruppoldingen / SO
Autor: Herzog, M.
DOI: <https://doi.org/10.5169/seals-15778>

Nutzungsbedingungen

Die ETH-Bibliothek ist die Anbieterin der digitalisierten Zeitschriften auf E-Periodica. Sie besitzt keine Urheberrechte an den Zeitschriften und ist nicht verantwortlich für deren Inhalte. Die Rechte liegen in der Regel bei den Herausgebern beziehungsweise den externen Rechteinhabern. Das Veröffentlichen von Bildern in Print- und Online-Publikationen sowie auf Social Media-Kanälen oder Webseiten ist nur mit vorheriger Genehmigung der Rechteinhaber erlaubt. [Mehr erfahren](#)

Conditions d'utilisation

L'ETH Library est le fournisseur des revues numérisées. Elle ne détient aucun droit d'auteur sur les revues et n'est pas responsable de leur contenu. En règle générale, les droits sont détenus par les éditeurs ou les détenteurs de droits externes. La reproduction d'images dans des publications imprimées ou en ligne ainsi que sur des canaux de médias sociaux ou des sites web n'est autorisée qu'avec l'accord préalable des détenteurs des droits. [En savoir plus](#)

Terms of use

The ETH Library is the provider of the digitised journals. It does not own any copyrights to the journals and is not responsible for their content. The rights usually lie with the publishers or the external rights holders. Publishing images in print and online publications, as well as on social media channels or websites, is only permitted with the prior consent of the rights holders. [Find out more](#)

Download PDF: 08.08.2025

ETH-Bibliothek Zürich, E-Periodica, <https://www.e-periodica.ch>

14. Swiss Railways' double track Aar Bridge at Ruppoldingen / SO

Owner and project management: Swiss Federal Railways,
Region 2 (Lucerne)

Designer and resident engineer: Dr. Max Herzog, Aarau
(collab. B. Fent)

Contractor: Locher & Cie AG, Zürich, and Rüeegg Bau AG,
Olten, in joint-venture

Dimensions:

length: 320 m

spans: 32 + 40 + 46 + 62 + 80 + 60 m

width: 10.7 m

Superstructure: six span continuous single-cell box-girder
with variable height above the river

Substructure: slender piers with elliptic cross-section and
box-type abutments

Foundations:

— southern abutment and land piers on stepped footings in
shallow depth

— river piers each on two bored piles of 3.0 m diameter and
40 m length

— northern abutment on two bored piles of 1.75 m diameter
and 18 respectively 38 m length

Quantities:

excavation: 3'000 m³

formwork: 11'500 m²

concrete: 5'000 m³

reinforcement: 620 t

prestressing steel: 180 t

sheet piling: 1'800 m²

years of construction: 1977 – 1978




Fig. 4 Construction phase




Fig. 1 Plan




Fig. 2 Longitudinal section

Introduction

To permit the realization of a rigid time-table on Switzerland's main line a new line has to be built between Olten and Rothrist. The Ruppoldingen Bridge is situated immediately southwards of the Born Tunnel and crosses the Aar River near Aarbrugg at about 45 degrees skew. The bridge as-built was chosen from a design competition among five consulting engineers.

Design and Construction

Special features worth mentioning are:

Slurry piles of 3.0 m diameter were a first in the country (concrete cube strength 40 N/mm² at 90 days)

The river piers' cross-section was verified in hydraulic model tests

Instead of steel bearings concrete hinges were built (cube strength 100 N/mm² at 90 days, extreme working stress 70 N/mm²)

Jumbo tendons (system VSL) consisting of 33 normal strands with 0.6" diameter ($0.65 \beta_z \cdot A_s = 5600 \text{ kN}$) and of 37 compact strands with 0.6" diameter (7500 kN) respectively Construction of the box-girder in several steps with section lengths of 20 - 45 m (southern half in 1977 and northern half in 1978):

- 1) Bottom slab of constant thickness in transverse direction (0.30 - 0.70 m) and webs of constant thickness (0.70 m) on normal scaffolding only as wide as the box-section
- 2) Top slab of variable thickness in transverse direction (0.30 - 0.50 m)
- 3) After construction of all box-sections for half the bridge length the tendons were pushed into previously cast ducts and the shrinkage gaps were closed. Five days later 50 per cent of the final prestressing force were applied
- 4) Cantilever slabs were cast with help of an overhead travelling formwork
- 5) After construction of the cantilever slabs for half the bridge length the full prestressing force was applied and the tendon ducts were grouted

There is a full splice of tendons between the two halves of the superstructure

Specified concrete cube strength of 50 N/mm² at 28 days (60 N/mm² at 90 days) was reached under strict control

The bridge has no fixed bearings. It is elastically restrained by the piers' bending stiffness

The design was checked against the most recent developments in the understanding of variable-amplitude fatigue loading and strength

Measurements

Because of the bridge's importance a large program of measurements is under way. Besides the usual deflections also

- temperature distributions in several cross-sections
- reinforcement strains under prestressing and different loadings to obtain information on the local strain distribution in the box-girder's cross-sections next to the piers
- displacements of the superstructure and ground-relaxation under longitudinal forces
- concrete hinge rotations

and other values are measured systematically.




Fig. 3 Cross-sections



(M. Herzog) Fig. 5 Completed bridge