Zeitschrift: IABSE structures = Constructions AIPC = IVBH Bauwerke

Band: 6 (1982)

Heft: C-20: Structures in the United States

Artikel: Columbia River Bridge (Oregon - Washington, USA)

Autor: Blanchard, F.P.

DOI: https://doi.org/10.5169/seals-17571

Nutzungsbedingungen

Die ETH-Bibliothek ist die Anbieterin der digitalisierten Zeitschriften auf E-Periodica. Sie besitzt keine Urheberrechte an den Zeitschriften und ist nicht verantwortlich für deren Inhalte. Die Rechte liegen in der Regel bei den Herausgebern beziehungsweise den externen Rechteinhabern. Das Veröffentlichen von Bildern in Print- und Online-Publikationen sowie auf Social Media-Kanälen oder Webseiten ist nur mit vorheriger Genehmigung der Rechteinhaber erlaubt. Mehr erfahren

Conditions d'utilisation

L'ETH Library est le fournisseur des revues numérisées. Elle ne détient aucun droit d'auteur sur les revues et n'est pas responsable de leur contenu. En règle générale, les droits sont détenus par les éditeurs ou les détenteurs de droits externes. La reproduction d'images dans des publications imprimées ou en ligne ainsi que sur des canaux de médias sociaux ou des sites web n'est autorisée qu'avec l'accord préalable des détenteurs des droits. En savoir plus

Terms of use

The ETH Library is the provider of the digitised journals. It does not own any copyrights to the journals and is not responsible for their content. The rights usually lie with the publishers or the external rights holders. Publishing images in print and online publications, as well as on social media channels or websites, is only permitted with the prior consent of the rights holders. Find out more

Download PDF: 28.11.2025

ETH-Bibliothek Zürich, E-Periodica, https://www.e-periodica.ch



3. Columbia River Bridge (Oregon - Washington, USA)

Owners: States of Oregon and Washington

Designers: Sverdrup & Parcel and

Associates, Inc., St. Louis, MO

Contractors: Reidel International,

Portland, OR
Peter Kiewit Sons Co.,

Omaha, NB

S. J. Groves & Sons Co.,

Minneapolis, MN

Construction

About 5 years

Duration:

Service Date: Early 1983

Introduction

The I-205 Columbia River Bridge, one of the largest single posttensioned-concrete projects in the U.S.A., will be the final link in a circumferential highway east of Portland, Oregon and Vancouver, Washington. The dual structures, each 20.7 m wide with a 2.7 m pedestrian trail mounted between, are 2,286 m long on a curvilinear alignment. The main feature of the structures is the five-span continuous rigid-frame unit shown below. This unit is flanked on the north with eight 43 to 91 m long spans, and on the south by twelve 73 to 110 m long spans. Structure depths for these approach spans vary from 2 to 5.2 m.

Design

Final design followed a type study which recommended building the bridge using cast-in-place-on-falsework posttensioned box girders for the 536 m northern overbank approach and precast segmental cantilever posttensioned box girders for the remaining 1,750 m over the river. The super-structure segments, designed with 34.5 MPa concrete, were posttensioned transversely with 1,102 MPa bars and longitudinally with 1,800 MPa strand. A complete set of contract documents was prepared on this basis.

An early plate and pile load-test program, which followed a geotechnical study, indicated that the northern overbank approach and the two navigation span piers could be set in a dense conglomerate with allowable bearing pressures up to 958 kPa. Since this dense conglomerate dips sharply to the south, the southern portion of the structure was designed using steel H-piles seated in the conglomerate and driven to a capacity of 1,780 kN.

The bridge site is in an active seismic zone which led to the concept of designing the structure with a series of rigid frames. At the abutments and intermediate expansion joints, neoprene bumpers and high-strength rod restrainers were provided to mitigate any damage from a seismic event.

Construction

Three construction contracts have been awarded to date with a fourth (roadway wearing surface, expansion dams, and roadway lighting) to follow. Each contract contains a Value Engineering incentive Clause inviting contractor modifications (with the Owner's approval) if serviceability, maintainability, standardization, and economy are not compromised. All contractors exercised this option to some degree, with the major accepted revision being the substitution of a two-cell box girder in place of three cells as designed.

Pile Caps and Piers

The pile caps for the river spans were constructed using a bell-shaped form which the contractor substituted for the precast segmental-concrete bells as designed. In this operation the river bed was prepared by excavation and pile driving, a prefabricated reinforcing cage was inserted into the form, and the form was lowered to-grade over the piles and sealed. The remaining reinforcement and concrete work was then completed in-the-dry before tripping the form. Hollow pier shafts varying from 3 to 6.7 m diameter were then extended above the pile caps.




Fig. 1 Navigation span rigid frame





Fig. 2 Pile cap form

Superstructure

A visitor to the bridge site in mid-1980 would have been able to observe three separate construction operations for posttensioned concrete girders proceeding simultaneously. The northern overbank approach was being cast-in-place-on-falsework in 6 m segments, and continuously posttensioned. The main-channel rigid frame was being constructed by cast-in-place segmental cantilever methods (a contractor revision) and the southern approach was being constructed by precast segmental cantilever erection.

(F. P. Blanchard)



Fig. 3 Cast-in-place falsework Cast-in-place cantilever



Fig. 4 91 m cantilever