

**Zeitschrift:** IABSE structures = Constructions AIPC = IVBH Bauwerke  
**Band:** 10 (1986)  
**Heft:** C-36: Structures in Japan

**Artikel:** Komyoike pedestrian bridge, Osaka  
**Autor:** Mino, S.  
**DOI:** <https://doi.org/10.5169/seals-19855>

### **Nutzungsbedingungen**

Die ETH-Bibliothek ist die Anbieterin der digitalisierten Zeitschriften auf E-Periodica. Sie besitzt keine Urheberrechte an den Zeitschriften und ist nicht verantwortlich für deren Inhalte. Die Rechte liegen in der Regel bei den Herausgebern beziehungsweise den externen Rechteinhabern. Das Veröffentlichen von Bildern in Print- und Online-Publikationen sowie auf Social Media-Kanälen oder Webseiten ist nur mit vorheriger Genehmigung der Rechteinhaber erlaubt. [Mehr erfahren](#)

### **Conditions d'utilisation**

L'ETH Library est le fournisseur des revues numérisées. Elle ne détient aucun droit d'auteur sur les revues et n'est pas responsable de leur contenu. En règle générale, les droits sont détenus par les éditeurs ou les détenteurs de droits externes. La reproduction d'images dans des publications imprimées ou en ligne ainsi que sur des canaux de médias sociaux ou des sites web n'est autorisée qu'avec l'accord préalable des détenteurs des droits. [En savoir plus](#)

### **Terms of use**

The ETH Library is the provider of the digitised journals. It does not own any copyrights to the journals and is not responsible for their content. The rights usually lie with the publishers or the external rights holders. Publishing images in print and online publications, as well as on social media channels or websites, is only permitted with the prior consent of the rights holders. [Find out more](#)

**Download PDF:** 21.02.2026

**ETH-Bibliothek Zürich, E-Periodica, <https://www.e-periodica.ch>**



### 8. Komyoike Pedestrian Bridge, Osaka

**Owner:** Housing and Urban Development Corporation

**Designer:** Oriental Consultants Corporation, Limited

**Contractor:** Sumitomo Construction Co., Ltd.

**Dimensions:**

- Overall bridge length: 157.6 m
- Arch span length: 98.0 m
- Full deck width: 4.0 m–6.0 m
- Arch rise: 21.25 m
- Span of deck: 2.05 m + 27.75 m + 98.0 m + 27.75 m + 2.05 m

**Quantities of material used:**

- 2650 m<sup>3</sup> concrete (40N/mm<sup>2</sup>)
- 290 t steel (SD30) for reinforcement
- 33 t steel for prestressing
- 282 t steel for arch centre
- 230 t steel for scaffold and falsework

**Construction Period:** from June, 1983 to September, 1984

**Introduction**

The Komyoike Pedestrian bridge crosses a pond called Komyoike in the residential area in the Senpoku hills approximately 27 km south of Osaka, which have been developed by the Housing and Urban Development Corporation, Kansai branch office. In order to harmonize with the environment and also to provide a landmark to the developed areas, thoughtful consideration was given in the design of the bridge. Selected was a unique reinforced concrete balanced arch construction with post-tensioned half through deck.

**Design**

Considering the nature of the soil which consists of alternate clay and sand layers, the most important factor was to minimize the dead weight of the superstructure. To meet this requirement, the concrete deck was designed to be prestressed and continuous over the columns. The arch base was founded on 28 or 30 steel pipe piles, 800 mm in diameter and 21 m in length. Analytical calculation of the whole structure was carried out by space frame analysis.




Fig. 1 General view





Fig. 2 Cross sections

## Construction

Procedure of construction is shown in stage 1 to 4

### Stage 1


1. arch foundation completed
2. cable crane and steel pylons installed
3. arch centre for falsework erected with temporary stay cables



Stage 1

### Stage 2


1. temporary stay cables and steel pylons removed
2. hanger PC steel bars set and scaffold for tie cable constructed
3. tie cable set and introduced prestressing



Stage 2

### Stage 3

1. cast-in-situ concrete constructed
2. arch rings completed



Stage 3

### Stage 4

1. falsework for side span erected
2. slab completed and introduced prestressing
3. falsework removed and tie cable released
4. after surfacing, this bridge completed



(S. Mino) Stage 4




Fig. 3 View of the bridge completed