

**Zeitschrift:** IABSE reports = Rapports AIPC = IVBH Berichte

**Band:** 55 (1987)

**Artikel:** Cable-stayed bridge across the Elbe

**Autor:** Strasky, Jiri / Korenek, Miroslav / Mencl, Vojtech

**DOI:** <https://doi.org/10.5169/seals-42827>

### Nutzungsbedingungen

Die ETH-Bibliothek ist die Anbieterin der digitalisierten Zeitschriften auf E-Periodica. Sie besitzt keine Urheberrechte an den Zeitschriften und ist nicht verantwortlich für deren Inhalte. Die Rechte liegen in der Regel bei den Herausgebern beziehungsweise den externen Rechteinhabern. Das Veröffentlichen von Bildern in Print- und Online-Publikationen sowie auf Social Media-Kanälen oder Webseiten ist nur mit vorheriger Genehmigung der Rechteinhaber erlaubt. [Mehr erfahren](#)

### Conditions d'utilisation

L'ETH Library est le fournisseur des revues numérisées. Elle ne détient aucun droit d'auteur sur les revues et n'est pas responsable de leur contenu. En règle générale, les droits sont détenus par les éditeurs ou les détenteurs de droits externes. La reproduction d'images dans des publications imprimées ou en ligne ainsi que sur des canaux de médias sociaux ou des sites web n'est autorisée qu'avec l'accord préalable des détenteurs des droits. [En savoir plus](#)

### Terms of use

The ETH Library is the provider of the digitised journals. It does not own any copyrights to the journals and is not responsible for their content. The rights usually lie with the publishers or the external rights holders. Publishing images in print and online publications, as well as on social media channels or websites, is only permitted with the prior consent of the rights holders. [Find out more](#)

**Download PDF:** 08.08.2025

**ETH-Bibliothek Zürich, E-Periodica, <https://www.e-periodica.ch>**

## Cable-Stayed Bridge across the Elbe

Le pont haubané sur l'Elbe

Schrägseilbrücke über die Elbe

Jiri STRASKY  
Chief Design Engineer

Miroslav KORENEK  
Project Manager

Vojtech MENCL  
Chief Research Engineer

Dopravní stavby, Design and Construction Engineers  
Olomouc, Czechoslovakia

The highway Prague - Hradec Kralove crosses the river Elbe on the cable-stayed bridge near spa Podebrady. The 32.3 m wide bridge has three spans of lengths 61.6 + 123.2 + 61.6 m, the total length of the bridge being 253.0 m / see Fig.1 /. The two three-lane carriageways are carried by one structure which is formed by a box spine girder with large outer cantilevers supported by precast struts / see Fig.2 /. The stays are arranged in one axial plane. The 28.06 m high towers are formed by two twin cell steel columns, which are fixed in the deck. In the upper part of each column the stayes are anchored, the lower part of the columns is filled with concrete, which co-acts with steel.

The deck is constructed successively; first the spine box girder is assembled of precast segments, then the precast struts are erected and the outer cantilevers are cast / see Fig.3 /. The segments are 15.0 m wide, 2.5 m deep and 2.2 m long, the maximum weight of the segments is 60 tons. Along the central axis the deck slab is supported at intervals 2.2 m by prestressed tie rods transferring the force from the stays into the bottom corners of the box girder. Above the piers and at the ends of the bridge solid segments are designed. Precast inclined struts are formed by a slab which is strengthened by webs on its edges. In the longitudinal direction the deck is prestressed by cables of 6




Fig.1 Longitudinal /a/ and cross /b/ section of the bridge




Fig.2 Cross section of the deck

strands of 15.5 mm dia situated both in the top and bottom slab, in the transverse direction the top slab is prestressed by the same cables. The bottom slab is prestressed by bars only in the segments situated near supports.

Each stay consists of two cables of 18 /15/ strands of 15.5 mm dia of ultimate strength 1800 MPa. The strands are encased in steel tubes completely filled with cement grout, in which during construction compression is created. Prior to grouting, which is carried out after casting the outer cantilevers, the cables are tensioned to a high-load level. After the grout has cured, the cables are detensioned to a design level and the grout becomes a structural member.




Fig.3 Successive construction of the deck

The segments were match-cast on the fixed bed of length corresponding to 1/8 of the bridge length. The spine box girder is being assembled in two progressive cantilevers which start from the abutments and proceed to midspan. During erection of side spans each sixth segment is temporarily supported, during the erection of the central span the erected segments are hung on the stays. Further, symmetrically to the towers, the precast struts and outer cantilevers are cast. After casting the joint at the midspan the deck is additionally post-tensioned. The erection of the deck started in March 1987 and will be finished in autumn this year.