

Zeitschrift: IABSE reports = Rapports AIPC = IVBH Berichte
Band: 57/1/57/2 (1989)

Artikel: Strengthening of a bridge with epoxy beam and prestressed steel
Autor: Engelhardt, Victor L.
DOI: <https://doi.org/10.5169/seals-44304>

Nutzungsbedingungen

Die ETH-Bibliothek ist die Anbieterin der digitalisierten Zeitschriften auf E-Periodica. Sie besitzt keine Urheberrechte an den Zeitschriften und ist nicht verantwortlich für deren Inhalte. Die Rechte liegen in der Regel bei den Herausgebern beziehungsweise den externen Rechteinhabern. Das Veröffentlichen von Bildern in Print- und Online-Publikationen sowie auf Social Media-Kanälen oder Webseiten ist nur mit vorheriger Genehmigung der Rechteinhaber erlaubt. [Mehr erfahren](#)

Conditions d'utilisation

L'ETH Library est le fournisseur des revues numérisées. Elle ne détient aucun droit d'auteur sur les revues et n'est pas responsable de leur contenu. En règle générale, les droits sont détenus par les éditeurs ou les détenteurs de droits externes. La reproduction d'images dans des publications imprimées ou en ligne ainsi que sur des canaux de médias sociaux ou des sites web n'est autorisée qu'avec l'accord préalable des détenteurs des droits. [En savoir plus](#)

Terms of use

The ETH Library is the provider of the digitised journals. It does not own any copyrights to the journals and is not responsible for their content. The rights usually lie with the publishers or the external rights holders. Publishing images in print and online publications, as well as on social media channels or websites, is only permitted with the prior consent of the rights holders. [Find out more](#)

Download PDF: 21.02.2026

ETH-Bibliothek Zürich, E-Periodica, <https://www.e-periodica.ch>

Strengthening of a Bridge with Epoxy Beam and Prestressed Steel
Renforcement d'un pont avec de l'époxi et des fils d'acier précontraints
Instandstellung einer Stahlbrücke mit Epoxyharz und Stahldrahtvorspannung

Victor L. ENGELHARDT
Civil Engineer
D.E.R.
Curitiba, PR, Brazil



Victor L. Engelhardt, born 1936, received his civil and structural engineering degree at the Federal University of Paraná, Brazil. Expert in design, precast bridges and principally in bridge rehabilitation. In 1980 visited "Subway Engineering" JICA, Tokyo, Japan. Nowadays works as consultant in Engelhardt & Graf.

SUMMARY

The historical value of a metallic truss-frame "Warren-type" bridge us required a new process of bridge rehabilitation in 1975. Through the profiles that composed the lower chord, an epoxy beam was constructed with 40 steel wires, which was slightly prestressed with the objective of neutralizing the traction in the lower chord due to the structure's own weight. The epoxy mix that filled the space inside the deteriorated metallic profiles and the prestressed wires formed a new composite girder which had the characteristics required by the rehabilitation project.

RÉSUMÉ

La valeur historique du pont métallique en treillis, du genre "Warren", a encouragé le développement d'un nouveau procédé de réparation, en 1975. Sur la longueur des profilés métalliques, qui composent la longrine inférieure du pont, une poutre d'époxis à été construite. Elle se compose de 40 fils d'acier, lesquels ont été mis en légère précontrainte, avec pour objectif de supprimer la traction engendrée par le poids propre de la structure. Le mélange d'époxis a rempli l'espace vide situé entre les profilés métalliques détériorés et les fils d'acier précontraint ce qui forma une nouvelle poutrelle composite munie des caractéristiques nécessaires au bon achèvement du projet de récupération.

ZUSAMMENFASSUNG

Der historische Wert einer alten Stahlfachwerkbrücke des Typs "Warren" führte 1975 zu einer neuartigen Lösung für deren Instandstellung. Zusammen mit den vorhandenen Profilen des Zuggurtes wurde ein Verbundbalken hergestellt, mit einer Epoxy-Zwischenfüllung und einer Längsvorspannung aus 40 Stahldrähten, welche, leicht vorgespannt, die Zugbeanspruchung infolge Eigengewicht neutralisieren. Der neue Verbundbalken verhielt sich in den vergangenen 13 Betriebsjahren äusserst zufriedenstellend.



1. INTRODUCTION

There is a metallic bridge over Nhundiaquara river on the Paraná coast, Brazil, near the Serra do Mar that was built in 1912. This bridge is used for urban traffic in the historical city of Morretes and is the initial point of Graciosa road a tourist attraction as it is the pioneer way from to the Curitiba highlands. (900 meters of altitude)

Its superstructure consists of a double metallic truss-frame "Warren" type with a 35.20 meters span and rests on a masonry infrastructure of excellent quality. Due to the proximity of the sea, lack of maintenance and total carelessness the bridge structure was so thoroughly eroded by the corrosion that its crumbling was foreseen even without traffic.

In 1964 an attempt to rehabilitate the bridge was carried out by a contractor using conventional methods but soon the results proved inefficient. Again the bridge had to be closed to the traffic from 1972 to 1975 when the Paraná's Highway State Department, D.E.R/Pr, decided to use its own work force to rehabilitate de bridge.




Fig. 1 General View

2. DESIGN AND EXECUTION

The rehabilitation design and execution was carried out in 1975 by engineer Victor L. Engelhardt, following these procedures:

2.1 Careful examination of all the structure showed that

2.2.1 The truss-frame lower chord was almost completely deteriorated due the corrosion.

2.1.2 The truss-frame lower joints were seriously damaged by the corrosion.

2.1.3 The metallic beams which supported the wood road surface were in an advanced stage of corrosion and could not be strenghtened (they were substituted by new parts).

2.1.4 The truss-frame components over deck plate were, in general, in acceptable conditions under structural point of view.




Fig. 2 Corrosion details



Fig. 3 Lower joints

2.2 Experiments at the DER/PR Laboratory

Several experiments were conducted with resins and epoxy structural adhesives using aggregate in several proportions as well as lightweight aggregate. Several series of samples were tested in different proportions resulting in:

- f_{cj} = average tension of rupture under compression with 'j' days;
- f_{tj} = average tension of rupture to traction with 'j' days;
- \bar{C}_m = average tension of adherence between steel and epoxy mix;
- γ' = specific weight.

2.2.1 Results of the first series of experiments

MISTURE (weight)	f_{c7} N/mm ²	f_{c21} N/mm ²	f_t N/mm ²	γ' g/cm ³
SIKA-DUR 32:SAND 1:0.5	57.4	-	51.7	2.10
SIKA-DUR 32:SAND 1:1	49.3	54.9	40.9	2.22
SIKA-DUR 32:SAND 1:2	28.9	-	-	2.26

Materials utilized:

- Sika-Dur 32
- Sand (from Curitiba)

2.2.2 Results of the second series of experiments

MISTURE	f_{c7} N/mm ²	γ' g/cm ³
SIKA-DUR 32:ISOPROPIL 1:3	24.9	1.073
1:4	15.6	1.037
1:5	13.2	0.993

Material utilized:

- Sika-Dur 32
- Isopropil spheres



2.2.3 Results of the third series of experiments

Materials utilized: Sika-Dur 32 - Isopropil Spheres - Steel CP-150 RN

Objective: Obtain the tension of adherence between steel and mix.

Results: Average tension obtained in the experiments. $\bar{\sigma}_{ad} = 11.52 \text{ N/mm}^2$

2.3 Solution adopted

- Cleaning with sand blast all the structure.
- Use new metallic reinforcements mainly in knots and superior chord.
- Through the profiles that composed the lower chord an epoxy beam was constructed with 40 steel wires $\phi 5 \text{ mm}$ which was slightly prestressed in order to neutralize the traction in the lower chord due the structure's own weight. The epoxy mix that filled the space inside the prestressed wires and the original profiles in addition to its great resistance for compressing and traction efforts due to its high adherence power, worked in order to form an unique block composite by old structure and reinforcements introduced.
- The compression tensions obtained with the samples moulded with the mix utilized in the rehabilitation were greater than ones obtained in the laboratory experiments as shown by the values indicated below:

Mixed design - 1:4 (Sika-Dur 32: Isopropil Spheres)

Moulding in 21/11/75 and rupture 28/11/75

Average tension obtained $t_{c7m} = 19.65 \text{ N/mm}^2$

Standard deviation $\delta = 1.59$

Maximum tension $f_{c7max.} = 21.24 \text{ N/mm}^2$

Minimum tension $f_{c7min.} = 18.06 \text{ N/mm}^2$

Specific weight $\gamma^1 = 0.965 \text{ g/cm}^3$

The 1:4 proportion mix volume was the first one indicated in view of its reduced specific weight, high adherence and facility of execution.








Fig. 4 and 5 Execution details


3. STRUCTURAL PLAN



ELEMENTS	ORIGINAL		WITH REINFORCEMENT	
	S M ² *E-4	I M ⁴ *E-5	S M ² *E-4	I M ⁴ *E-5
1 a 6	79,54	3820	119.70	7.852
7 = 21	80.89	3820	115.10	6.111
8 = 10 = 12	62.55	4.320	62.55	4.320
14 = 16 = 18	"	"	"	"
20	"	"	"	"
9 = 19	75.34	2.797	93.35	2.797
11 = 17	63.87	1.890	79.01	1.890
13 = 15	48.48	1.234	55.64	1.234
22 a 29	183.30	22.770	183.30	22.770
30 a 37	32.20	1.850	32.20	1.850
38 a 45	—	—	7.86	
46 a 53	—	—	315.17	9.33



4. THE STRUCTURE BEHAVIOR



In order to check the structure's behavior another serie of tests were executed with an overload truck weighting 129.7 kN, in january 1989.

The tests were realized with the truck parking in 7 stations, at same time the deformations were indicated through a deflectometer (accuracy 1/100 mm) installed in the middle of the bridge.

With these results were possible to confront the deflections obtained by project and practically. We can observe in figure above that the deformations measured were always smaller than the theoretical deformations, consequently showing the good performance of the structure.

5. CONCLUSION

The structure has been constantly observed for 13 years, subject to normal loads and its performance has proved excellent in regard to deformation and also to the knots rehabilitated and the adherence between epoxy resine and metallic parts.