

Zeitschrift: IABSE reports = Rapports AIPC = IVBH Berichte
Band: 81 (1999)

Artikel: Design and detailing for durability: concrete subways and underpasses
Autor: Chakrabarti, Amarnath / Roy, B.C. / Mondal, S.S.
DOI: <https://doi.org/10.5169/seals-61437>

Nutzungsbedingungen

Die ETH-Bibliothek ist die Anbieterin der digitalisierten Zeitschriften auf E-Periodica. Sie besitzt keine Urheberrechte an den Zeitschriften und ist nicht verantwortlich für deren Inhalte. Die Rechte liegen in der Regel bei den Herausgebern beziehungsweise den externen Rechteinhabern. Das Veröffentlichen von Bildern in Print- und Online-Publikationen sowie auf Social Media-Kanälen oder Webseiten ist nur mit vorheriger Genehmigung der Rechteinhaber erlaubt. [Mehr erfahren](#)

Conditions d'utilisation

L'ETH Library est le fournisseur des revues numérisées. Elle ne détient aucun droit d'auteur sur les revues et n'est pas responsable de leur contenu. En règle générale, les droits sont détenus par les éditeurs ou les détenteurs de droits externes. La reproduction d'images dans des publications imprimées ou en ligne ainsi que sur des canaux de médias sociaux ou des sites web n'est autorisée qu'avec l'accord préalable des détenteurs des droits. [En savoir plus](#)

Terms of use

The ETH Library is the provider of the digitised journals. It does not own any copyrights to the journals and is not responsible for their content. The rights usually lie with the publishers or the external rights holders. Publishing images in print and online publications, as well as on social media channels or websites, is only permitted with the prior consent of the rights holders. [Find out more](#)

Download PDF: 01.04.2026

ETH-Bibliothek Zürich, E-Periodica, <https://www.e-periodica.ch>



Design and Detailing for Durability – Concrete Subways and Underpasses

A CHAKRABARTI

Chief Engineer, Central PWD
Presently in charge of
Mass Rapid Transit System Cell
Ministry of Urban Affairs &
Employment, Govt. of India,
Delhi, INDIA



Amarnath Chakrabarti born in Dec. 1947 got his Civil Engineering Degree from University of Calcutta and passed M.I. Struct. E. (London) qualifying exam in 1973. Has been involved in the design and construction management of Infrastructure facilities particularly in the field of highway structures and urban transit projects.

B C ROY

Executive Director
Consulting Engineering
Services (India) Limited
New Delhi, India



B C Roy born in March, 1944 got his Civil Engineering from Jadavpur University, Calcutta, Masters from IIT Kharagpur and Graduate Research from New Castle University, Australia. He has extensive experience in Planning, Design and Implementation of bridges, flyovers, underpasses and metros, high rise buildings, industrial structures, domes and shells structure etc.

S S MONDAL

Superintending Engineer
Central PWD presently
Project Manager, PWD
Govt. of Delhi
New Delhi, INDIA



S S Mondal born in Dec., 1950 received his Civil Engineering Degree from University of Calcutta. Has been in charge of design and construction of bridges and flyovers in urban area. He is currently the project manager of two major flyover projects in New Delhi, INDIA

Summary

Durability of structures refer to its ability to endure weathering action, attack by various substances and conditions to which it may be exposed over the serviceable life. Many of the conditions that cause structures to lack durability, are not immediately apparent. Basic causes are attributable to input of harmful materials, aggressive environment or inappropriate design, detailings or construction. This paper discusses design and detailing features for pedestrian and vehicular underpasses, under construction, to improve durability aspect. As such, approach to design and detailing for three cases of subway/underpass projects in India, was to design for durability, faster implementation and simplified construction technique. Projects discussed in this paper are pedestrian subway at Rajagarden, integrated pedestrian & vehicular underpass at Punjabi Bagh in Delhi and underground mass rapid transit system, in Calcutta.

1. INTRODUCTION

Electrically operated intracity Mass Rapid Transit System, whether underground, at grade or elevated is rare in India. Such facilities, to a limited extent, have been built very recently in few cities and some are still in planning/implementation stages. At present transport system in India, primarily cater for motorised vehicles both for mass and individual transport. Most of the major intersections and corridors of the major cities in India are very congested. To ease such congested situations, transport authorities are planning for multilevel grade separators for pedestrian and vehicular movements and also to increase the average speed of movement. Such grade separated movement warrants pedestrian subway, or vehicular underpass. Their planning and design however need to cater for existing underground utilities, narrow roads, lack of space for traffic diversion ground water table etc.

In spite of appropriate and detailed implementation planning and schedules, with cast-in-situ construction, pedestrian subways need at least twelve months for completion, which is too long a period to have restricted traffic movement in an intersection. In order to minimise the traffic hindrance, reduce construction period & on site activities, to improve the quality of construction, etc, the use of prefabricated concrete elements has been introduced for Rajagarden pedestrian subway at Delhi as shown in Fig. 1.




Fig. 1 : Precast Subway showing different Units

For the construction of Punjabi Bagh underpass or for that matter the construction of Calcutta Metro, use of modern systems e.g. TBM or NATM might have been a better choice particularly to maintain normal traffic movement during construction. However, as construction using TBM or NATM is very expensive and need capital intensive equipments, cut and cover technique are more favoured

both for vehicular underpass or metros. Out of the different forms of temporary/permanent walling, diaphragm wall has been used predominantly.

For underpasses in Delhi or Metro in Calcutta being constructed or constructed, diaphragm walling have been used not only to facilitate other construction activities but also to bear load either in partial or/in total as the case may be i.e. semi-integrated or integrated as shown in Fig. 2 and Fig. 3.

Parameters for design, detailing and construction works method have been carefully selected in these designs and are briefed in the following sections.

2. CONSTRAINTS AND APPROACH

During the planning for design and construction of these structures, number of constraints were taken care of proper implementation as :

- High ground water table
- Existing major underground utilities
- Limited space available for construction in busy traffic corridor



- To keep the intersection traffic moving during construction phase
- Minimise construction time to open the carriageways as soon as possible for the convenience of traffic.




Fig. 2 : Cross Section of Underpass and Pedestrian Subway at Intersection




Fig. 3 : Cross Section of Metro : Non-Station Portion (Semi-Integrated Approach)

In addition, as these underground structures, with a high ground water table warrants dry condition inside the underpass or subway, for serviceability and user's comfort, the following aspects were also taken care in the design:

- Water tight joints & adequate water proofing treatment
- System of draining out the seepage and/or rain water from open areas
- Adequate ventilation, forced or natural, particularly for pedestrian subway




Fig. 5 : Typical Joint between Precast units in Longitudinal Direction




Fig. 6 : Details of Joint between Precast Unit and Cast-in-Situ Arch




Fig. 7 : R C Details of Unit - 2

Fig. 6 indicates the methodology of water tight integration of the longitudinal subway at its ends with the approach stairs in the perpendicular direction.

For the integration of the bottom slab with the precast unit (**Fig. 1** and **Fig. 7**), the same has been shaped and detailed such that the connection can be treated as hinge with provision for rotation of the ends of the bottom slab at its ends. The reinforcement detailing has been done to ensure the hinge behaviour.

Number of prefabricated elements being small, precasting of the elements are done near the site to avoid long/distant travel during transportation. As such elements can be easily transported by a mobile crane and each element can be easily installed in proper place with integration of the other elements. Use of various methods as detailed in sketches ensure water tight subway. However provision for a sump with pumping arrangement has been kept for draining out of the rain water that will pour inside the subway through the open approaches.

4. UNDERPASS

As mentioned earlier, the cases considered are Calcutta Metro and integrated pedestrian and vehicular underpasses in Punjabi Bagh, New Delhi. As the design approach for both the cases are more or less similar except the changes required for functional performance as semi integrated and fully integrated structural system. The important aspects which are directly related to the serviceability and durability are described in the subsequent sections.

4.1 Guide Walls

The guide walls are not an integral part of the underpass system, yet they are important in exercising control on the construction of the diaphragm walls. The guide walls should be heavy with appropriate depth and contractor should take proper care of the compaction of filling after completion of the guide walls. Accordingly, the design of the guide walls in both the cases are to consider the following aspects :

- Appropriate depths to avoid excessive and cavity formation
- Due consideration to ground water table
- Appropriate head of bentonite slurry with proper viscosity and gel strength
- Avoid movement of the guide walls to ensure verticality of diaphragm wall
- Proper orientation of the guide wall as shown below




Fig. 8 : Guide Walls

Accordingly, the depth of guide walls in the range of 1.2 to 1.5 m have been adopted.

4.2 Panel Width

Concrete diaphragm walls are generally constructed in panels, wherein each panel acts as an independent unit. While selecting the size of the panel width in both cases the Calcutta Metro with clayey strata and Punjabi Bagh underpass with granular strata, attempt was made to mobilize the strut forces as per the design load.

The panel width has been kept to a size so that one row of horizontal strut only for each panel will be sufficient for the safety of excavation. However the panel width can not be less than the single bite widths of grab. Panel width of approx. 3 m has been found to be cost effective and technically optimum.

In addition, while selecting the size of the panels, the following points had been considered :

- Continuous diaphragm walls need Robust shear connectors which are difficult to provide.
- Concreting have to be completed before the setting or significant stiffening of the panel (Not more than 3 to 3 ½ hours)
- Removal of stop-ends before the concrete is set.
- To reduce the formation of shrinkage crack (Though the curing is under humid conditions the longer panel lengths will be subjected to shrinkage effects)
- Safety of the excavated trench and easy handling of the reinforcement cage.

4.3 Water Tightness

Diaphragm wall are subjected to both soil and water pressures and thereby impermeability of wall panels is of great concern for durable structural system. The various factors affecting the water tightness are :

- Quality of the concrete with regard to maximum aggregate size and water cement ratio (20 m aggregate & w/c ratio 0.6)
- Formation of cracks particularly for longer panels



- Leakage from the joints attributable to differential deflection between the panels
- Semi circular vertical joints at ends of each panel

Sometimes shear transfer devices are used to help in reducing the differential deflection between consecutive panels and thereby improves water tightness. But to provide shear connector between two panels is difficult and cumbersome. Accordingly, in most of the underpasses or metro, water has been allowed to seep through the joints.

The leakage through joint was not critical for Calcutta Metro as the water tightness was ensured through second wall. While in Delhi, cement grout has been proposed at the back of the joint to ensure water tightness to the extent possible as shown in Fig. 9. In addition an elaborate arrangement for drainage has been made to keep the underpass dry, serviceable and durable as shown in Fig. 10a and 10b.

4.4 Buoyancy

As the ground water table is very high in both the cases the structure had to be designed to resist the uplift due to buoyancy forces. In Calcutta Metro this was not critical in most of the stretches excepting the station areas, primarily due to overburden on top of the box as shown in the figure.




Fig. 9

In case of Punjabi Bagh underpass the uplift becomes highly critical particularly in open to sky approaches due to the absence of adequate overburden. Alternative approaches have been considered to ensure stability

- To put additional weight in the form of iron ore filling
- To provide tension piles to resist the uplift forces.
- To release the water pressure by providing suitable collection of underground water and draining thereof.

Each system has its own merits and demerits though the authors favour the combination of the last two

4.5 Reinforcement Details

The design and detailing of the reinforcement caging shall take into consideration the following aspects :

- Smooth bar bending with adequate cover
- Bar placement to avoid the trapping of bentonite slurry
- Proper securing of the insert boxes avoiding any protrusion
- Appropriate detailing to cater for the handling




Fig. 10a and 10b

5. CONCLUSION

Experience shows that improvements in standard of controls has a direct effect on improving the standard of the finished product and thereby its durability. Thus the various aspects concerning the durability, serviceability of the specific project shall be detailed out at the project conception stage prior to design and detailing.