Zeitschrift: The Swiss observer: the journal of the Federation of Swiss Societies in

the UK

Herausgeber: Federation of Swiss Societies in the United Kingdom

Band: - (1946)

Heft: 1057

Artikel: Swiss business ventures in England

Autor: [s.n.]

DOI: https://doi.org/10.5169/seals-692762

Nutzungsbedingungen

Die ETH-Bibliothek ist die Anbieterin der digitalisierten Zeitschriften auf E-Periodica. Sie besitzt keine Urheberrechte an den Zeitschriften und ist nicht verantwortlich für deren Inhalte. Die Rechte liegen in der Regel bei den Herausgebern beziehungsweise den externen Rechteinhabern. Das Veröffentlichen von Bildern in Print- und Online-Publikationen sowie auf Social Media-Kanälen oder Webseiten ist nur mit vorheriger Genehmigung der Rechteinhaber erlaubt. Mehr erfahren

Conditions d'utilisation

L'ETH Library est le fournisseur des revues numérisées. Elle ne détient aucun droit d'auteur sur les revues et n'est pas responsable de leur contenu. En règle générale, les droits sont détenus par les éditeurs ou les détenteurs de droits externes. La reproduction d'images dans des publications imprimées ou en ligne ainsi que sur des canaux de médias sociaux ou des sites web n'est autorisée qu'avec l'accord préalable des détenteurs des droits. En savoir plus

Terms of use

The ETH Library is the provider of the digitised journals. It does not own any copyrights to the journals and is not responsible for their content. The rights usually lie with the publishers or the external rights holders. Publishing images in print and online publications, as well as on social media channels or websites, is only permitted with the prior consent of the rights holders. Find out more

Download PDF: 24.11.2025

ETH-Bibliothek Zürich, E-Periodica, https://www.e-periodica.ch

SWISS BUSINESS VENTURES IN ENGLAND.

British Brown-Boveri Limited, 75, Victoria Street, S.W.1, has on order for the Great Western Railway Company a 2,500 h.p. 90 m.p.h. Gas Turbine-Electric Locomotive. The locomotive is being designed and constructed by Brown, Boveri and Co., Ltd., Baden, Switzerland.

A similar but somewhat smaller capacity locomotive, illustrated below, was built by the same firm some five years ago for the Swiss Federal Railway. technical achievement aroused considerable interest all over the world, as it was the first time this new form of engine was adopted for traction work. It is the only locomotive of its kind in regular service.

The principal details of the G.W.R. locomotive are as under:

Continuous nett output of the gas turbine unit

2,500 h.p.

Tractive effort at the wheel rim at starting

33,000 lbs. from 0—20 m.p.h. 13,000 lbs. at 60 m.p.h. and 8,800 lbs. at 90 m.p.h.

Maximum continuous speed ...

continuously

90 m.p.h.

Weight in running order ...

about 113 tons.

Weight for braking ...

about 113 tons.

Furnace fuel oil.

Adhesive weight

about 75 tons.

Length overall

Fuel

65 ft. 6 ins.

Trailing weight corresponding to tractive effort of 13,000 lbs. at 60 m.p.h. is about 850 tons, but a trailing weight of 1,200 tons

can be hauled at speeds up to 40 m.p.h. continuously and 50 miles intermittently.

locomotive carries The The locomotive carries sufficient fuel for 250 miles, viz., suitable for non-stop runs from Paddington to Plymouth.

In the gas turbine-electric locomotive the heat content of the fuel oil is directly converted into mechanical energy without, for instance, the working medium of water as in the case of the steam locomotive. The mechanical energy thus produced is transmitted electrically to the locomotive driving axles.

The gas turbine unit consists essentially of: An axial flow compressor, a heat exchanger, a combustion chamber and a gas turbine. The compressor is driven by the turbine and the air which is compressed to about 45 lbs./sq.in.g. in the compressor is fed to the com-


bustion chamber through the heat exchanger. the combustion chamber the fuel oil is consumed with only a portion of this air, the remaining (much greater portion) air bye-passes the actual combustion chamber and mixes with the products of combustion in order to reduce the combustion temperature to a maximum temperature of about 1,100° F. before the turbine. This mixture of air and products of combustion is expanded through the turbine and useful work produced. The turbine exhaust gases escape to the atmosphere through the roof of the locomotive after passing through the heat exchanger. In the heat exchanger a portion of the heat in the exhaust gases is transferred to the air being delivered to the combustion chamber, the temperature of the air being thus raised to about 500° F.

At full load the turbine develops about 10,300 h.p., the compressor absorbs about 7,800 h.p. and the difference of 2,500 is transmitted to the generator set through a reduction gear.

The function of the electrical equipment is to convert the available mechanical energy produced by the gas turbine unit into electrical energy and to transmit this to the driving axles by means of electric motors.

The locomotive is carried on two six-wheel bogies, the outer axles of each bogie being driven by series type D.C. motors completely suspended to reduce the unsprung weight to a bare minimum. Driving cabs giving unobstructed look-out are at both ends as the locomotive is equally suitable for running in both directions without turning. One man control is provided, as well as standard G.W.R. safety arrangement for co-ordination with line signals.

Compared with a highly efficient express steam locomotive, such as is at present being used on the Great Western line, the fuel consumption of the gas turbine-electric locomotive will be less than half for equal work done.



Swiss Federal Railways 2,200 h.p. Gas Turbine Electric Locomotive at the Gare de l'Est, Paris.